

ADDENDUM

Salish Cliffs Golf Course RFP 2 September 2022

The following shall be included as allowances in the response to the above referenced Bid:

- 1) Repair Sod
 - Quantity: Two (2) AC additional Ryegrass sod
 - Item: Ryegrass Sod
 - Contractor shall use "Per Acre" sod pricing in place.

- 2) Cart Path Replacement
 - Quantity: 2,500 LF cart path
 - Item: 9FT width concrete cart path
 - Contractor shall use Unit Price (LF) in place for Concrete Cart Path.

- 3) Bunker Drainage
 - Quantity: 2,500 LF bunker drainage
 - Item: 4" Perforated drainage pipe, including trenching, gravel, and installation
 - Contractor shall use Unit Price (LF) in place for bunker drainage (installed)

The following is a Clarification on Bunker Construction;

BUNKER SHAPING:

Remove grass/sod from bunker surrounds as indicated in the bunker detail on the plan documents. Grade and shape all bunker slopes, bottoms and surrounds using the existing soils from the bunkers and imported clean soil provided by OWNER to re-contour the new bunker shapes as directed by the ARCHITECT.

As discussed during the pre-bid meeting of 31 August 2022, the greenside bunker of Hole #13 is our example for all the new bunker shapes. Some bunkers may be deeper as directed by the ARCHITECT.

BUNKER DRAINAGE:

Remove and replace existing bunker drainage, including trenching, drainage pipe and drain line gravel.